MATERIAL OR PRODUCT	NEV. TEST NO.	TEST	SAMPLE FREQUENCY	LOCATION OR TIME OF SAMPLING	SIZE OF SAMPLE	REMARKS
Borrow / Embankment	115	Resistance "R" value	One per 40,000 m³ (50,000 yd³) or fraction thereof for qualifying the materials	Source Requirement Test	Sample one full, large canvas sample sack	Submit to Materials Division for testing
	101 or 108	Harv. Mini. or Proctor	101 or 108 and 104 to be run every 25 compaction tests, minimum	After final compaction		101 or 108 and 104 to be run concurrently
	104	Specific Gravity				
	102 or 103	Density	One per 4,000 m³ (5,000yd³) of embankment, but not less than one per day, per lift	After final compaction		
Select Borrow	115	Resistance "R" value	One per 40,000 m³ (50,000 yd³) or fraction thereof for qualifying the materials	Source Requirement Test	Sample one full, large canvas sample sack	Submit to Materials Division for testing
	101 or 108	Harv. Mini. or Proctor	101 or 108 and 104 to be run every 25 compaction tests, minimum	After final compaction		101 or 108 and 104 to be run concurrently
	104	Specific Gravity				
	102 or 103	Density	One per 4,000 m³ (5,000 yd³) of embankment, but not less than one per day, per lift	After final compaction		
	206	Sieve Analysis	One per day		Table 5.3	
Original Ground and Base of Cuts	101 or 108	Harv. Mini. or Proctor	101 or 108 and 104 to be run every 25 compaction tests, minimum	After final compaction		101 or 108 and 104 to be run concurrently
	104	Specific Gravity				
	102 or 103	Density	One per 3,350 m² (4,0000 yd²), but not less than one per day; or one per structure for footings, pipes, headwalls,etc.	After final compaction		

MATERIAL OR PRODUCT	NEV. TEST NO.	TEST	SAMPLE FREQUENCY	LOCATION OR TIME OF SAMPLING	SIZE OF SAMPLE	REMARKS
Backfill	101 or 108	Harv. Mini. or Proctor	101 or 108 and 104 to be run every 25 compaction tests, minimum	At the discretion of the Resident Engineer		101 or 108 and 104 to be run concurrently
	104	Specific Gravity				
	102 or 103	Density	One per 750 m³ (1,000 yd³) or fraction thereof per structure, or one per lift	At the discretion of the Resident Engineer		
	206	Sieve Analysis	One per 750 m³ (1,000 yd³) or fraction thereof		Table 5.3	
Granular Backfill	206	Sieve Analysis		Source Requirement Test	Sample one full, large canvas sample sack	Submit to Materials Division for testing
	210/211/212	Atterberg Limits		Source Requirement Test		Submit to Materials Division for testing
	AASHTO T289 AASHTO T288	pH Value Resistivity		Source Requirement Test		Submit to Materials Division for testing
	101 or 108	Harv. Mini. or Proctor	101 or 108 and 104 to be run every 25 compaction tests, minimum	At the discretion of the Resident Engineer		101 or 108 and 104 to be run concurrently
	104	Specific Gravity				
	102 or 103	Density	One per 750 m³ (1,000 yd³) or fraction thereof per structure, or one per lift	At the discretion of the Resident Engineer		
	206	Sieve Analysis	One per 750 m³ (1,000 yd³) or fraction thereof		Table 5.3	
	210/211/212	Atterberg Limits	One per 750 m³ (1,000 yd³) or fraction thereof			

MATERIAL OR PRODUCT	NEV. TEST NO.	TEST	SAMPLE FREQUENCY	LOCATION OR TIME OF SAMPLING	SIZE OF SAMPLE	REMARKS
MSE Backfill	206	Sieve Analysis	One per 7,650 m³ (10,000 yd³), one per stockpile minimum	Source Requirement Test	Sample on full, large canvas sample sack	Submit to Materials Division for Testing
	210/211/212	Atterberg Limits	One per 7,650 m³ (10,000 yd³), one per stockpile minimum	Source Requirement Test		Submit to Materials Division for Testing
	AASHTO T289 AASHTO T288 AASHTO T291 AASHTO T290	pH Value Resistivity Chlorides Sulfates	One per 7,650 m³ (10,000 yd³), one per stockpile minimum	Source Requirement Test		Submit to Materials Division for testing
	101 or 108	Harv. Mini. or Proctor	101 or 108 and 104 to be run every 25 compaction tests, minimum	At the discretion of the Resident Engineer		101 or 108 and 104 to be run concurrently
	104	Specific Gravity				
	102 or 103	Density	One per 750 m³ (1,000 yd³) or fraction thereof per structure, or one per lift	At the discretion of the Resident Engineer		
	206	Sieve Analysis	One per 750 m³ (1,000 yd³) or fraction thereof		Table 5.3	
	210/211/212	Atterberg Limits	One per 750 m³ (1,000 yd³) or fraction thereof			
Slurry Backfill	206	Sieve Analysis	One per 750 m³ (1,000 yd³) or fraction thereof		Table 5.3	
	428	Compressive Strength	One per 150 m³ (200 yd³) or fraction thereof	See Nev. T425, Standard Method of Test for Sampling Fresh Concrete. At the discretion of the Resident Engineer		Three 6" X 12" cylinders (28 day) are required for each sample. More may be made for information. Submit to designated lab for testing
	431 or 432	Air Content by Volumetric or Pressure	One per 150 m³ (200 yd³) or fraction thereof	First test to be taken within first two loads		
	438	Slump	At the discretion of the Resident Engineer			Slump is run whenever consistency is questionable. See Section 207

MATERIAL OR PRODUCT	NEV. TEST NO.	TEST	SAMPLE FREQUENCY	LOCATION OR TIME OF SAMPLING	SIZE OF SAMPLE	REMARKS
Drain Backfill	AASHTO T96	% of Wear (500 rev.)		Source Requirement Test	Sample two full, large canvas sample sacks	Submit to Materials Division for testing
	206	Sieve Analysis	One per 750 m³ (1,000 yd³) or one per project minimum	At time of use, jobsite stockpile	Table 5.3	
Types 1, 2 and 3 Base (For Type 3, See Special	115	Resistance (R Value)		Source Requirement Test	Sample two full, large canvas sample sacks	Submit to Materials Division for testing
Provisions)	AASHTO T96	% Wear (500 Rev.)		Source Requirement Test		Submit to Materials Division for testing
	206	Sieve Analysis	One per day or one per 1,800 t (2,000 tons) when nonuniform material	Class A: From roadway directly behind spreader Class B: From processed windrow, just prior to final lay down	Table 5.3	For small quantity, location and frequency of sample are at the discretion of the Resident Engineer
	210/211/212	Atterberg Limits	One per day or one per 1,800 t (2,000 tons) when non-uniform material			For small quantity, location and frequency of sample are at the discretion of the Resident Engineer
	230	Fractured Face	One per day			For small quantity, location and frequency of sample are at the discretion of the Resident Engineer
	112	Moisture	One per day or one per 1,800 t (2,000 tons) when nonuniform material	Moisture tests should be taken from the windrow or stockpile after the material has been weighed, but prior to adding any additional water in the field		Results for payment purposes. Moisture tests need to represent what was weighed
	101 or 108	Harv. Mini. or Proctor	101 or 108 and 104 to be run every 25 compaction tests, minimum	On roadway, after trimming and final compaction		101 or 108 and 104 to be run concurrently. For small quantity, location and frequency of sample are at the discretion of the Resident Engineer. For
	104	Specific Gravity				Type A only: Depth checks taken during density test but for information only. Record depths on Daily Construction Report.
	102 or 103	Density	One per 1800 t (one per 2,000 tons) or fraction thereof or one per lift	On roadway, after trimming and final compaction		

NEV. TEST NO.	TEST	SAMPLE FREQUENCY	LOCATION OR TIME OF SAMPLING	SIZE OF SAMPLE	REMARKS
	Straightedge Tolerances Section 302	One per lane km (two per lane mile)	Finished surface		Record results on Daily Construction Report
AASHTO T96	% of Wear (500 rev.)		Source Requirement Test	Sample four full, large canvas sample sacks	Submit to Materials Division for testing
206	Sieve Analysis	One per 900 t (1,000 tons)	Road mixed: From processed material, prior to adding cement Plant mixed: From conveyors, prior to adding cement	Table 5.3	During production, aggregate is sampled for informational purposes
227	Sand Equivalent	One per day or one per 900 t (1,000 tons) when questionable material			
237	Compressive Strength	Three on the first day of production, one per day thereafter. If questionable material, more tests may be required at the discretion of the Resident Engineer			Compressive strength for information only.
112	Moisture	One per 1,800 t (2,000 tons)			Record moistures on Daily Construction Report
101 or 108	Harv. Mini. or Proctor	101 or 108 and 104 to be run every 25 compaction tests, minimum	On roadway, after trimming and final compaction		101 or 108 and 104 to be run concurrently. Depth checks taken during density test for information only. Record depths on Daily
104	Specific Gravity				Construction Report
102 or 103	Density	One per 1,800 t (one per 2,000 tons) or fraction thereof or one per lift	On roadway, after trimming and final compaction		
	Straightedge Tolerances Section 304	One per lane km (two per lane mile) per lift	Finished surface		Record results on Daily Construction Report
	TEST NO. AASHTO T96 206 227 237 112 101 or 108 104	TEST NO. TEST Straightedge Tolerances Section 302 AASHTO T96 Sieve Analysis 227 Sand Equivalent Compressive Strength 112 Moisture Harv. Mini. or Proctor 104 Specific Gravity 102 or 103 Density Straightedge Tolerances	TEST NO. TEST SAMPLE FREQUENCY Straightedge Tolerances Section 302 AASHTO T96 % of Wear (500 rev.) 206 Sieve Analysis One per 900 t (1,000 tons) 227 Sand Equivalent One per day or one per 900 t (1,000 tons) when questionable material 237 Compressive Strength Three on the first day of production, one per day thereafter. If questionable material, more tests may be required at the discretion of the Resident Engineer 112 Moisture One per 1,800 t (2,000 tons) 101 or 108 Harv. Mini. or Proctor 101 or 108 and 104 to be run every 25 compaction tests, minimum 104 Specific Gravity 105 One per 1,800 t (one per 2,000 tons) or fraction thereof or one per lift Straightedge Tolerances One per lane km (two per lane mile) per lift	TEST SAMPLE FREQUENCY TIME OF SAMPLING Straightedge Tolerances Section 302 AASHTO T96 Sieve Analysis One per 900 t (1,000 tons) Sieve Analysis One per 900 t (1,000 tons) Sieve Analysis One per 900 t (1,000 tons) Road mixed: From processed material, prior to adding cement Plant mixed: From conveyors, prior to adding cement Three on the first day of production, one per day thereafter. If questionable material, more tests may be required at the discretion of the Resident Engineer Moisture One per 1,800 t (2,000 tons) Harv. Mini. or Proctor One per 1,800 t (2,000 tons) Three on the first day of production, one per day thereafter. If questionable material, more tests may be required at the discretion of the Resident Engineer One per 1,800 t (2,000 tons) On roadway, after trimming and final compaction Specific Gravity One per 1,800 t (one per 2,000 tons) or fraction thereof or one per lift Straightedge Tolerances One per lane km (two per lane mile) per lift Finished surface	TEST NO. TEST SAMPLE FREQUENCY TIME OF SAMPLING SIZE OF SAMPLE Straightedge Tolerances Section 302 AASHTO T96 % of Wear (500 rev.) Sieve Analysis One per 900 t (1,000 tons) Sieve Analysis One per 900 t (1,000 tons) 227 Sand Equivalent One per day or one per 900 t (1,000 tons) when questionable material may be required at the discretion of the Resident Engineer Three on the first day of production, one per day thereafter. If questionable material, more tests may be required at the discretion of the Resident Engineer Moisture One per 1,800 t (2,000 tons) Harv. Mini. or Proctor Density One per 1,800 t (one per 2,000 tons) or fraction thereof or one per lift one per lift Finished surface Finished surface Finished surface Finished surface Finished surface Finished surface Sample four full, large canvas sample sacks Table 5.3 Tone on the first day of production, one per day thereafter. If questionable material, more tests may be required at the discretion of the Resident Engineer One per 1,800 t (0,000 tons) Tone on the first day of production of the Resident Engineer One per 1,800 t (0,000 tons) On roadway, after trimming and final compaction Straightedge Tolerances One per 1,800 t (one per 2,000 tons) or fraction thereof or one per lift Finished surface

MATERIAL OR PRODUCT	NEV. TEST NO.	TEST	SAMPLE FREQUENCY	LOCATION OR TIME OF SAMPLING	SIZE OF SAMPLE	REMARKS
Pulverized Base and Surface (Roadbed	112	Moisture	One per 5,900 m ² (7,000 yd ²) or fraction thereof	On roadway, after final compaction		Record moistures on sieve analysis form
Modification)	101 or 108	Harv. Mini. or Proctor	101 or 108 and 104 to be run every 25 compaction tests, minimum	On roadway, after final compaction		101 or 108 and 104 to be run concurrently. Depth checks for information only. Record depths on Daily Construction Report
	104	Specific Gravity				
	102 or 103	Density	One per 5,900 m ² (7,000 yd ²) or fraction thereof	On roadway, after final compaction		
	206	Sieve Analysis	One per 5,900 m ² (7,000 yd ²) or fraction thereof	After final pulverization by removing a composite sample of the pulverized surface at randomly selected sites prior to adding cement	Table 5.3	
		Cement Distribution	One per lane km (two per lane mile)			Phenolphthalein test for information only. Record results on Daily Construction Report
Shouldering Material	206	Sieve Analysis	One per day or one per 1,800 t (2,000 tons) when non-uniform material; one per day for coldmilled material	At belt or stockpile. Coldmilled material from windrow	Table 5.3	
	210/211/212	Atterberg Limits	One per day or one per 1,800 t (2,000 tons) when questionable material			
Blotter Sand, Sand in Stockpile	206	Sieve Analysis	One per project per source	At belt or stockpile	Table 5.3	
Aggregate for Plantmix Bituminous Base, Surface, Open-Graded, Permeable Base and Premix	AASHTO T96	% of Wear (500 rev.)		Mix Design Submittal and/or Source Requirement Test	Sample two full, large canvas sample sacks from each size for each mix design	Submit to Materials Division for testing

TABLE 5.1 - MINIMUM REQUIRED SAMPLES AND TESTS - PROJECT

MATERIAL OR PRODUCT	NEV. TEST NO.	TEST	SAMPLE FREQUENCY	LOCATION OR TIME OF SAMPLING	SIZE OF SAMPLE	REMARKS
Aggregate for Plantmix Bituminous	206	Sieve Analysis		Mix Design Submittal and/or Source Requirement Test		Submit to Materials Division for testing
Base, Surface, Open-Graded, Permeable Base and Premix Cont.	210/211/212	Atterberg Limits		Mix Design Submittal and/or Source Requirement Test		Submit to Materials Division for testing
Transmit Summ	230	Fractured Face		Mix Design Submittal and/or Source Requirement Test		Submit to Materials Division for testing
	AASHTO T104	Soundness, Sodium	Coarse and fine aggregate	Mix Design Submittal and/or Source Requirement Test		Submit to Materials Division for testing
	AASHTO T85	Absorption	Coarse aggregate	Mix Design Submittal and/or Source Requirement Test		Submit to Materials Division for testing
	AASHTO T84	Specific Gravity	Fine aggregate	Mix Design Submittal and/or Source Requirement Test		Submit to Materials Division for testing
	AASHTO T85	Specific Gravity	Coarse aggregate	Mix Design Submittal and/or Source Requirement Test		Submit to Materials Division for testing
	206	Sieve Analysis	One per 4,500 t (5,000 tons) of each size produced, minimum one test per five production days for each size aggregate	From belt or stockpile	Table 5.3	Tests must be run prior to marination. For information only
	210/211/212	Atterberg Limits	One per 4,500 t (5,000 tons) of each size produced, minimum one test per five production days for each size aggregate	From belt or stockpile		Tests must be run prior to marination
	230	Fractured Face	One per 4,500 t (5,000 tons) of each size produced, minimum one test per five production days for each size aggregate	From belt or stockpile		Tests must be run prior to marination
	111	Absorption of Coarse Aggregate	One per five production days per size	From belt or stockpile		Tests must be run prior to marination
	112	Moisture	Minimum one per size per week	From belt of stockpile during marination		Record moistures in Marination Diary. For information only.

MATERIAL OR PRODUCT	NEV. TEST NO.	TEST	SAMPLE FREQUENCY	LOCATION OR TIME OF SAMPLING	SIZE OF SAMPLE	REMARKS
Aggregate for Plantmix Bituminous Base, Surface, Open-Graded, Permeable Base and Premix Cont.		Lime Distribution	One per size per project. If questionable material, more tests may be required at the discretion of the Resident Engineer	From belt or stockpile during marination	J 22	Phenolphthalein test during production. Record in Marination Diary
Recycled Asphalt Pavement (RAP) for Plantmix Bituminous Surface	AASHTO T30	Mechanical Analysis of Extracted Aggregate		Mix Design Submittal	Sample two full, large canvas sample sacks from each size for each mix design	Submit to Materials Division for testing
	AASHTO T164	Extraction of Asphalt Binder		Mix Design Submittal		Submit to Materials Division for testing
		Sieve Analysis	One per 4,500 t (5,000 tons) of each size produced, minimum one test per five production days for each size aggregate	From belt or stockpile	Table 5.3	Verify material meets specified sieve requirements
Permeable Base (Asphalt Treated)	206	Sieve Analysis	One per 1,800 t (2,000 tons), or one per day minimum	Section 303 of Special Provisions	Table 5.3	Material remaining from Nev. T761
	761 306	Bitumen Ratio Moisture Content	One per 1,800 t (2,000 tons), or one per day minimum			
		Straightedge Tolerances Section 303	One per lane km (two per lane mile)	Finished surface		Record results on Daily Construction Report

MATERIAL OR PRODUCT	NEV. TEST NO.	TEST	SAMPLE FREQUENCY	LOCATION OR TIME OF SAMPLING	SIZE OF SAMPLE	REMARKS
Premix	AASHTO T269	Percent Air Voids of Compacted Mixture	One per project	From jobsite stockpile	Three full 6" X 12" cylinders, this sample will cover AASHTO T269 and Nev. T303	Submit to Materials Division for testing
	T303	Stabilometer	One per project	From jobsite stockpile		Submit to Materials Division for testing
	206	Sieve Analysis	One per 1,800 t (2,000 tons) or one per day minimum	From coldfeed belt at plant during production	Table 5.3	
Plantmix Bituminous Base and Surface	206	Sieve Analysis	One per 900 t (1,000 tons) for the first two production days. Reduce to one per 1,800 t (2,000 tons) if specification material is continuously produced or one per day minimum. If two consecutive tests are out of specifications, return to one per 900 t (1,000 tons)	Section 106	Table 5.3	Material remaining from Nev. T761
	112	Moisture	One per day	From coldfeed belt at plant during production		For information only, record moistures on testers portion of Daily Plant Report
	761 306	Bitumen Ratio Moisture Content	One per 900 t (1,000 tons) for the first two production days, reduce to one per 1,800 t (2,000 tons) if consistently within jobmix tolerances or one per day minimum. NOTE: Immediately test another sample to verify the results before making plant adjustment	Composite sample from behind the paver, prior to rolling		
	324	Theoretical Maximum Density (Rice)	One for each one-half day of production (a.m. and p.m.)	Composite sample from behind the paver, prior to rolling		For Method B compaction only

MATERIAL OR PRODUCT	NEV. TEST NO.	TEST	SAMPLE FREQUENCY	LOCATION OR TIME OF SAMPLING	SIZE OF SAMPLE	REMARKS
Plantmix Bituminous Base and Surface Cont.	AASHTO T269	Percent Air Voids of Compacted Mixture	Sample first three days of paving; then one per 9,000 t (10,000 tons) or twice per week, whichever is less		Three full 6" X 12" cylinders, this sample will cover AASHTO T269 and Nev. T303 and T341	Submit to Materials Division for testing
	303	Stabilometer	One per 9,000 t (10,000 tons) or twice per week, whichever is less; sample first three days of paving			Submit to Materials Division for testing
	341	Indirect Tensile Strength and Retained Strength	One per 9,000 t (10,000 tons) or twice per week, whichever is less; sample first three days of paving			Submit to Materials Division for testing. Materials Division will determine the frequency of performing the test
	335 or 750	Density	Section 402	Random locations per Test Method		See specifications for required test method and density requirements. Nev. T336 will be used to correlate the thin layer density gauge (Nev. T335)
		Straightedge Tolerance Section 402	One per lane km (two per lane mile)	Finished surface		Record results on Daily Construction Report
	446	Evaluation of Profiles	Section 402	Section 402		Complete within 48 hours after placement
Plantmix Bituminous Open-Graded Surface	206	Sieve Analysis	One per 900 t (1,000 tons) or one per day minimum	From augers at paver or windrow in front of paver	Table 5.3	Material remaining from Nev. T761
Surface	112	Moisture	One per day	From coldfeed belt at plant during production		For information only, record moistures on testers portion of Daily Plant Report
	761 306	Bitumen Ratio Moisture Content	One per 900 t (1,000 tons) or one per day minimum	From augers at paver or windrow in front of paver		

MATERIAL OR PRODUCT	NEV. TEST NO.	TEST	SAMPLE FREQUENCY	LOCATION OR TIME OF SAMPLING	SIZE OF SAMPLE	REMARKS
Plantmix Bituminous Open-Graded Surface Cont.		Straightedge Tolerance Section 402	One per lane km (two per lane mile)	Finished surface		Record results on Daily Construction Report
	446	Evaluation of Profiles	Section 402 and 403	Section 402 and 403		Complete within 48 hours after placement
Cold Recycle		Sieve Analysis	One per lane km (two per lane mile)	Windrow	Table 5.3	Verify material meets specified sieve requirements
	750	Density	Section 404	Random locations per Test Method		
	112	Moisture	Two per day	Windrow		One in a.m. and one in p.m., for information only. Record moistures on Daily Construction Report
	112	Moisture	See Section 404	Section 404		(Moisture for cores)
	759	Field Viscosity Section 404	One per truck and one per trailer	Approximate midpoint / mid depth of the load		Sampled by contractor and observed by NDOT representative
		Straightedge Tolerance Section 404	One per lane km (two per lane mile)	Finished surface		Record results on Daily Construction Report
Surface Treatment Screenings (Chips)	AASHTO T96	% Wear (500 Rev.)	One per project, per source, per supplier	Source Requirement Test	Sample two full, large canvas sample sacks per source per supplier	Submit asphalt and aggregate to Materials Division for testing
	209	Stripping	One per project, per source, per supplier	Aggregate source and asphalt supplier specific	1 gallon of asphalt	Submit 1 gallon of asphalt and aggregate sample to Materials Division for testing
	206	Sieve Analysis	One per 1,800 t (2,000 tons)	From jobsite stockpiles	Table 5.3	
	228 (CA T227)	Cleanness Value	One per 1,800 t (2,000 tons)	From jobsite stockpiles		

MATERIAL OR PRODUCT	NEV. TEST NO.	TEST	SAMPLE FREQUENCY	LOCATION OR TIME OF SAMPLING	SIZE OF SAMPLE	REMARKS
Surface Treatment Screenings (Chips)	230	Fractured Face	One per 1,800 t (2,000 tons), minimum one per project	From jobsite stockpiles		
Cont.	759	Field Viscosity Section 408	One per truck and one per trailer	Approximate mid depth / midpoint of the load		Sampled by contractor and observed by NDOT representative
Micro-Surfacing	AASHTO T96	% Wear (500 Rev.)		Mix Design Submittal and/or Source Requirement Test		Submit to Materials Division for testing
	AASHTO T104	Soundness, Sodium	Coarse and fine aggregate	Mix Design Submittal and/or Source Requirement Test		Submit to Materials Division for testing
	206	Sieve Analysis		Mix Design Submittal and/or Source Requirment Test		Submit to Materials Division for testing
	210/211/212	Atterberg Limits		Mix Design Submittal and/or Source Requirement Test		Submit to Materials Division for testing
	227	Sand Equivalent		Mix Design Submittal and/or Source Requirement Test		Submit to Materials Division for testing
	230	Fractured Face		Mix Design Submittal and/or Source Requirement Test		Submit to Materials Division for testing
	206	Sieve Analysis	One per 1,800 t (2,000 tons) or one per day minimum	From belt or stockpile	Table 5.3	
	210/211/212	Atterberg Limits	One per 1,800 t (2,000 tons) or one per day minimum	From Jobsite Stockpiles		
	227	Sand Equivalent	One per 1,800 t (2,000 tons) or one per day minimum	From Jobsite Stockpiles		
	230	Fractured Face	One per 1,800 t (2,000 tons) or one per day minimum	From Jobsite Stockpiles		

TABLE 5.1 - MINIMUM REQUIRED SAMPLES AND TESTS - PROJECT

MATERIAL OR PRODUCT	NEV. TEST NO.	TEST	SAMPLE FREQUENCY	LOCATION OR TIME OF SAMPLING	SIZE OF SAMPLE	REMARKS
Concrete Aggregates	AASHTO T96 AASHTO T104	% Wear (500 Rev.) Soundness, Sodium	Contact Materials Division	Source Requirement Test Source Requirement Test		Contact Materials Division
	AASHTO T19	Unit Weight		Source Requirement Test		For lightweight aggregate only
	AASHTO T21	Organic Impurities		Source Requirement Test		
	ASTM C330	Staining Material		Source Requirement Test		For lightweight aggregate only
	ASTM C87	Mortar Making Properties		Source Requirement Test		
	AASHTO T112	Clay Lumps	One per project, per source, per coarse size	Samples to be taken in conjunction with source acceptance samples	Sample one full, large canvas sample sack for each size	Submit to Materials Division for testing
	206	Sieve Analysis	Pavement: One per size per 6,000 m² (7,000 yd²) of pavement or fraction thereof Structures: One per size per 225 m³ (300 yd³) of concrete or fraction thereof	Belt sample whenever possible. Structures: Sample stockpiles before beginning concrete production	Table 5.3	
	227	Sand Equivalent	Pavement: One per day, when questionable material, one per 6000 m² (7000 yd²) of pavement or fraction thereof Structures: One per 225 m³ (300 yd³), or when questionable material, one per day			Fine Aggregate
	228 (CA T227)	Cleanness Value	Pavement: One per week (5 days production) Structures: One per 225 m³ (300 yd³) (not required on minor and incidental concrete), or one per week with single placements over 225 m³ (300 yd³)			Commercial sources to be tested two days prior to anticipated use. Coarse Aggregate
	112	Moisture	Minimum of one per day per size	Prior to beginning concrete production		For information only

NEV. TEST NO	TEST	SAMPLE FREQUENCY	LOCATION OR TIME OF SAMPLING	SIZE OF SAMPLE	REMARKS
492	Specific Gravity	Minimum of one per source per mix design			For information only
493	Absorption	Minimum of one per source per mix design			For information only
428	Compressive Strength	One set per 75 m³ (100 yd³). Minimum one set per pour	See Nev. T425, Standard Method of Test for Sampling Fresh Concrete. At the discretion of the Resident Engineer		Three cylinders (28 day) are required for each sample. Two additional cylinders (7 day) will be required for MSE panels. More may be made for information. Submit to designated lab for testing
431 or 432	Air Content by Volumetric or Pressure	One per 75 m³ (100 yd³) or fraction thereof	First test to be taken within first two loads		
438	Slump	One per 75 m³ (100 yd³) or fraction thereof	First test to be taken within first two loads		Slump is run concurrently with fabrication of cylinders; also whenever required or consistency is questionable. If failing results, vehicle should stop unloading, test results verified and corrective action taken
435	Unit Weight	One per 75 m³ (100 yd³) or fraction thereof		0.03 m ³ (1 ft ³)	Unit weight is run concurrently with fabrication of cylinders
	Field Measurements of concrete cover on deck reinforcement Section 502	Minimum of 12 measurements for each section of deck pour	Six measurements are to be taken before placing concrete and six measurements at the same locations shall be taken after concrete has been placed		Record measurements on Daily Construction Report
206	Sieve Analysis	Minimum one per day	Sample during production	Table 5.3	
	TEST NO. 492 493 428 431 or 432 438	TEST NO. TEST 492 Specific Gravity 493 Absorption 428 Compressive Strength 431 or 432 Air Content by Volumetric or Pressure 438 Slump 435 Unit Weight Field Measurements of concrete cover on deck reinforcement Section 502	TEST NO. TEST SAMPLE FREQUENCY 492 Specific Gravity Minimum of one per source per mix design 493 Absorption Minimum of one per source per mix design 428 Compressive Strength One set per 75 m³ (100 yd³). Minimum one set per pour 431 or 432 Air Content by Volumetric or Pressure 438 Slump One per 75 m³ (100 yd³) or fraction thereof 438 One per 75 m³ (100 yd³) or fraction thereof 435 Unit Weight One per 75 m³ (100 yd³) or fraction thereof 436 Minimum of 12 measurements for each section of deck pour	TEST NO. TEST SAMPLE FREQUENCY TIME OF SAMPLING 492 Specific Gravity Minimum of one per source per mix design 493 Absorption Minimum of one per source per mix design 428 Compressive Strength One set per 75 m³ (100 yd³). Minimum one set per pour 431 or 432 Air Content by Volumetric or Pressure 438 Slump One per 75 m³ (100 yd³) or fraction thereof loads 438 Pield Measurements of concrete cover on deck reinforcement Section 502 Minimum of 12 measurements for each section of deck pour shall be taken after concrete has been placed	TEST NO. TEST SAMPLE FREQUENCY TIME OF SAMPLING SIZE OF SAMPLE 492 Specific Gravity Minimum of one per source per mix design 493 Absorption Minimum of one per source per mix design 428 Compressive Strength One set per 75 m³ (100 yd³). Minimum one set per pour 431 or 432 Air Content by Volumetric or Pressure 438 Slump One per 75 m³ (100 yd³) or fraction thereof Pressure 439 Air Content by Volumetric or Pressure 430 One per 75 m³ (100 yd³) or fraction thereof Pressure 430 Slump One per 75 m³ (100 yd³) or fraction thereof Size to be taken within first two loads 435 Unit Weight One per 75 m³ (100 yd³) or fraction thereof Six measurements are to be taken before placing concrete and six measurements or ondeck reinforcement Section 502 436 Six measurements are to be taken before placing concrete and six measurements at the same locations shall be taken after concrete has been placed

MATERIAL OR PRODUCT	NEV. TEST NO.	TEST	SAMPLE FREQUENCY	LOCATION OR TIME OF SAMPLING	SIZE OF SAMPLE	REMARKS
Pneumatically Placed Concrete (Shotcrete)	ASTM C42	Compressive Strength for Cores	Special Provisions, Section 660	Special Provisions, Section 660		Submit cores to Materials Division for testing
Self Consolidating Concrete (SCC)	416	Compressive Strength	One set per 75 m³ (100 yd³) or fraction thereof. Minimum one set per pour	See Nev. T425, Standard Method of Test for Sampling Fresh Concrete. At the discretion of the Resident Engineer		Three cylinders (28 day) are required for each sample. More may be made for information. Submit to designated lab for testing
	416	Air Content	One per 75 m³ (100 yd³) or fraction thereof	First test to be taken within first two loads		When possible, fabrication of cylinders, air content, unit weight, slump flow and j-ring to be run concurrently
	416	Unit Weight	One per 75 m³ (100 yd³) or fraction thereof			
	417	Slump Flow / VSI (Visual Stability Index)	One per 75 m³ (100 yd³) or fraction thereof	Test first three loads then one per 75 m³ (100 yd³)	0.03 m ³ (1 ft ³)	
	418	J-Ring / Slump cone	One per 75 m³ (100 yd³) or fraction thereof	First test to be taken within first two loads		
Portland Cement Concrete for Pavement	442	Flexural Strength	One per day	Platform at the plant or on roadway when using transit trucks		Three strength specimens are made from each sample and are broken in the field. Break one beam at age of 10 days and one beam at age of 28 days. The spare beam should be used in case of faulty break or if it is desired to vary the breaking schedule
	438	Slump	One per 600 m³ (750 yd³) but not less than one per day	Platform at the plant or on roadway when using transit trucks		Slump is run concurrently with fabrication of cylinders; also when consistency is questionable
	439	Ball Penetration	One per truck	Platform at the plant or on roadway when using transit trucks		This test is at the discretion of Resident Engineer; for concrete consistency only; Section 409
	435	Unit Weight	One per 600 m³ (750 yd³) but not less than one per day	Platform at the plant or on roadway when using transit trucks	0.03 m ³ (1 ft ³)	Unit weight and air content to be run concurrently on different portions of the same sample

TABLE 5.1 - MINIMUM REQUIRED SAMPLES AND TESTS - PROJECT

MATERIAL OR PRODUCT	NEV. TEST NO.	TEST	SAMPLE FREQUENCY	LOCATION OR TIME OF SAMPLING	SIZE OF SAMPLE	REMARKS
Portland Cement Concrete for Pavement Cont.	431 or 432	Air Content by Volumetric or Pressure	One per 600 m³ (750 yd³) but not less than one per day	Platform at the plant or on roadway when using transit trucks	0.03 m ³ (1 ft ³)	
	428	Compressive Strength	One per 600 m³ (750 yd³) but not less than one per day	Platform at the plant or on roadway when using transit trucks		Concurrent with other tests. Three cylinders (28 day); more may be made for information
	446	Evaluation of Profiles	Section 409	Section 409		
		Straightedge Tolerance Section 409	One per lane km (two per lane mile)	At the discretion of the Resident Engineer		Record results on Daily Construction Report
	AASHTO T148	Length of Drilled Cores	One per 300 m (1,000 ft), or fraction thereof, traffic lane, auxiliary lane or shoulder	At random locations		Cores taken by Materials Division after profile grinding
		Dowel Bar Placement Section 409	All bars by MIT	At the discretion of the Resident Engineer		Performed by contractor. Two cores required per bar, one at each end
Grout for Post Tensioning	426	Flow Test	One per girder, minimum	At the point of discharge		If test fails, perform a retest at the vent or the opposite end of that girder
Ducts, Soilnails, Shear Keys, Dowel Holes and Ground Anchors	ASTM C39	Compressive Strength	Special Provisions, Section 503, 643 or 644	Special Provisions, Section 503, 643 or 644	Three 4" X 8" cylinders may be used in lieu of grout cubes	Submit to Materials Division for testing
Polymer Concrete	ASTM D4263	Moisture by Plastic Sheet Method	One per 90 m² (1,000 ft²) or portion thereof	At the discretion of the Resident Engineer		
	ACI 503R	Surface Soundness and Adhesion	One per 50 m² (60 yd²) or portion thereof	At the discretion of the Resident Engineer		Pull Off test

MATERIAL OR PRODUCT	NEV. TEST NO.	TEST	SAMPLE FREQUENCY	LOCATION OR TIME OF SAMPLING	SIZE OF SAMPLE	REMARKS
Polymer Concrete Cont.		Straightedge Tolerance Section 496	At the discretion of the Resident Engineer	At the discretion of the Resident Engineer		Record results on Daily Construction Report
	446	Evaluation of Profiles	Section 496	Section 496		
Stone for Riprap, Aggregate for Riprap Bedding and	AASHTO T96	% Wear (500 Rev.)		Source Requirement Test	Sample two full, large canvas sample sacks	Submit to Materials Division for testing. For riprap larger than Class 150, contact Materials Division
*Stone for Grouted Riprap	AASHTO T85	Specific Gravity		Source Requirement Test		Submit to Materials Division for testing
		Gradation		Visual Inspection Section 706		
		*Gradation and Grout Penetration	Section 706			
Asphaltic Products (Liquid Asphalts and Emulsions)			One sample for each delivery (this sample represents truck and trailer). For field viscosity testing, take one sample from each truck and one from each trailer. Section 106	From shipping vehicle after arrival on job and before or at time of unloading	1 liter (1 qt)	Submit to Materials Division for testing. To be sampled by contractor and observed by NDOT representative
			each track and one nom each trailer. Section 100		*1 gallon	*Pretest emulsion for cold recycling
Asphalt Cements			Section 106 for applicable frequencies	Samples of asphalt cement from a hotplant shall be taken from bituminous feed line at a suitable location between storage tank and bituminous metering device	1 liter (1 qt)	Submit to Materials Division for testing. To be sampled by contractor and observed by NDOT representative

MATERIAL OR PRODUCT	NEV. TEST NO.	TEST	SAMPLE FREQUENCY	LOCATION OR TIME OF SAMPLING	SIZE OF SAMPLE	REMARKS
Fly Ash		Section 702	One sample per contract per supplier	During unloading at jobsite	2 kg (4 lbs), one 4" X 8" cylinder may be used	Submit to Materials Division for testing. A certificate of compliance for each load is required, per the specifications. Manufacturer's test report is required. Samples are taken by the contractor's representative and witnessed by an NDOT representative.
Hydrated Lime	ASTM 1097		Not required, unless requested by Resident Engineer	During unloading at jobsite	2.5 kg (5 lbs)	Submit to Materials Division for testing. A certificate of compliance for each load is required, per the specifications. If required, samples are taken by the contractor's representative and witnessed by an NDOT representative.
Quicklime (Cold Recycle)	ASTM C977		One sample per contract per supplier	During unloading at jobsite	2.5 kg (5 lbs)	Submit to Materials Division for testing. A certificate of compliance for each load is required, per the specifications. Samples are taken by the contractor's representative and witnessed by an NDOT representative.
Portland Cement	ASTM C150		Pavement: One sample per 100,000 m² (120,000 yd²) of pavement Structures: One sample per type of cement per project per supplier	During unloading at jobsite	2 kg (4 lbs), one 4" X 8" cylinder may be used	Submit to Materials Division for testing. A certificate of compliance for each load is required, per the specifications. Cement is accepted for immediate use on the basis of Certificate of Compliance. Manufacturer's test report is required. Samples are taken by the contractor's representative and witnessed by an NDOT representative. Small quantities, at discretion of Resident Engineer.
Water (Cold Recycle, Concrete, etc.)			One sample per source	Submit according to specifications	Refer to specifications	Submit to Materials Division in clean glass or plastic container. No sample necessary if obtained from an obviously suitable source such as a domestic water supply. Sample still required for cold recycling

MATERIAL OR PRODUCT	NEV. TEST NO.	TEST	SAMPLE FREQUENCY	LOCATION OR TIME OF SAMPLING	SIZE OF SAMPLE	REMARKS
Reinforcing Steel		Section 713	Two samples of each bar size per manufacturer per project per year	Supplier shall furnish 2 samples of each bar size for testing. Random samples may be taken as provided for in Section 505	0.75 m (30 in)	Submit to Materials Division for testing. Show heat numbers on transmittal and state test procedure needed ASTM A706 or ASTM A615. Certified mill tests used for acceptance at jobsites
Prestressing Bars, Steel Strand, Wire, Anchorage Assemblies and Bar Couplers		Section 713	Sample per size and heat for prestressing bar; sample per manufactured reel for prestressing steel strand; sample per coil for prestressing wire; and sample per lot for anchorage assemblies and bar couplers	Section 713	Refer to specifications	Submit with each sample, a certification stating the manufacturer's minimum guaranteed ultimate tensile strength of the sample furnished
Corrugated Metal Pipe (CMP) and Structural Plate Pipe	AASHTO T65	Spelter Coating	Two per 150 m (500 ft) or fraction thereof	Random samples throughout shipment after delivery to job	50 mm (2 in) triangle	Submit to Materials Division for testing. Tests on base metal performed periodically in addition to coating test. Show mill analysis and heat number
Reinforced Concrete Pipe (RCP)		Fabricator Certificate				Fabricator must have yearly certification by Materials Division
Permanent Sign Posts		Section 627	One sample per project per supplier	After delivery to jobsite	0.3 m (1')	Submit to Materials Division for testing
Metal Fence Posts		Section 724	One sample per project per supplier	After delivery to jobsite	0.3 m (1') except t-posts, need one full post	Submit to Materials Division for testing. Include grade and class on transmittal
Guide Posts		Section 721	One sample per project per supplier	After delivery to jobsite	One full post	Submit to Materials Division for testing
Object Markers		Section 721	One sample per project per supplier	After delivery to jobsite	One full post	Submit to Materials Division for testing

MATERIAL OR PRODUCT	NEV. TEST NO.	TEST	SAMPLE FREQUENCY	LOCATION OR TIME OF SAMPLING	SIZE OF SAMPLE	REMARKS
Chain Link Fence		Section 724	Two pieces for each lot shipped to jobsite	Random samples from random spools after delivery to jobsite	0.3 m (1 ft) wide full height	Submit to Materials Division for testing
Woven Wire and Barbed Wire		Section 724	Woven Wire: Two pieces per 50 rolls or fraction thereof. Barbed Wire: Four pieces per 50 rolls or fraction thereof	Random samples from random spools after delivery to jobsite	Woven: Two sections wide full height. Barbed: 900 mm (3 ft) long	Submit to Materials Division for testing
Traffic Paint		Section 729	One per contract per manufacturer's lot	Upon delivery to jobsite	1 liter (1 qt) wide mouth metal can	Submit to Materials Division for testing. Sample each color. Epoxy: Sample each component. Include the manufacturer product code and batch on the transmittal. For waterborne paint, specify Type I or Type II
	511	Retroreflectivity Section 632	One per lane kilometer (three per lane mile) of stripe. Average five readings per location, minimum	1-2 weeks after application		
	510	Thickness Section 632	Two per day per color			Measured without beads
Pavement Marking Film (Tape)	512	Adhesion Section 634	One per lane kilometer (two per lane mile); miscellaneous items - arrows, only's, crosswalks, stop bars, etc. will be at the discretion of the Resident Engineer	Test within 48 hours of placement		
Traffic Beads		Section 730	One per project per manufacturer's lot	Upon delivery to jobsite	1 liter (1 qt) wide mouth metal can	Submit to Materials Division for testing. Include manufacturer's lot number and type on the transmittal